



## CONSTRUCTION NOTICE

### 9 MILE ROAD REHABILITATION, INKSTER RD TO BEECH RD

---

#### PROJECT HIGHLIGHTS:

- Asphalt pavement removal and concrete rubblization of existing roadway with hot mix asphalt resurfacing.
  - Underlying concrete pavement will be rubblized to serve as an aggregate base for a new hot mix asphalt surface for most of the project.
  - Inkster Rd / 9 Mile Rd intersection will be cold milled and resurfaced with hot mix asphalt during a weekend closure.
  - Four-lane section of 9 Mile Rd (just west of Beech Rd) will be reconstructed with revised lane configuration.
  - There will be no work at the Beech Rd / 9 Mile Rd intersection.
- Minor storm drainage improvements utilizing primarily open-ditch design.
- New 4-foot shoulders will be constructed to allow for bike lanes along 9 Mile Rd.
- Minor sidewalk ramp improvements will be completed.
- Most guardrail runs will be replaced along 9 Mile Rd to meet current design standards.
- Work will begin in mid-March 2020 and continue through October 2020.
- Construction on 9 Mile Rd will be performed “part-width”, maintaining one-lane one-way for local traffic only. Eastbound-only local traffic will be maintained for the first half of the project, and westbound-only local traffic will be maintained for the second half of the project. Both directions of through traffic will be detoured up to 10 Mile Rd (highlighted in **GREEN** in the attached map).
- This \$2,010,000 project is being funded with \$607,000 Federal funds and \$1,403,000 City road bond funds.

For all construction related inquiries, please contact our Construction Engineer overseeing the project:

**Cara Parks**, Construction Engineer

[Cara.parks@ohm-advisors.com](mailto:Cara.parks@ohm-advisors.com)

(734) 466-4420